

SEASON EXTENSION HARDWARE : MESURES IN INCHES & FEET

Mini-tunnel covering 2 beds 78" X 100'	Pic	Pieces / 100'	Price/unit	Total
1/2 inch EMT electrical conduit. Piece of 10' + 2' welded on		20	7,00 \$	140,00 \$
1/2 inch fender washer		40	0,20 \$	8,00 \$
1/2 inch rebar cut in 30" pieces		40	2,00 \$	80,00 \$
Bailing twine cut in length of 20'		20	0,15 \$	3,00 \$
6mil UV treated greenhouse plastic 14' X 118'		1	170,00 \$	170,00 \$
Total				401,00 \$
Price per square foot 400\$ \ (6.5 X 100)				\$0,62 per sq. ft.
Caterpillar tunnel covering 4 beds 16' X 100'. Bow spaced every 5'				
1 1/4 inch Galvanum steel bows		20	46,50 \$	930,00 \$
5/8 inch rebar cut in 30" pieces		40	2,20 \$	88,00 \$
Polyester rope roll of a 1,000 foot		1	45,50 \$	45,50 \$
130' Purlin Strap		1	32,00 \$	32,00 \$
5/16 inch Carabiners		40	0,75 \$	30,00 \$
Stainless steel anchor plates with 5/8 inch hole to pass the rebar		40	3,50 \$	140,00 \$
8 feet T-post		4	9,50 \$	38,00 \$
6mil UV treated greenhouse plastic 24' X 130'		1	280,00 \$	280,00 \$
Total				1 583,50 \$
Price per square foot 1583\$ \ (16' X 100')				\$0,99 per sq. ft.